



NLC - The Next Linear Collider Project




**Main Linac
RF System
Overview**



Chris Adolphsen


Next Linear Collider Test Accelerator

- Construction Started in 1993 Using 'First Generation' RF Component Designs
- Goals: RF System Integration Test of a Section of NLC Linac and the Efficient, Stable and Uniform Acceleration of a NLC-like Bunch Train
- In 1997, with All Three RF Units Operational, Successfully Demonstrated 15% Beam Loading Compensation of a 120 ns Bunch Train to $< 0.3\%$



100-100000

NLCTA RF Unit



NLC Linac RF Unit

Induction Modulator

Low Level RF System

One 490 KV 3-Turn Induction Modulator

Eight 2 KW TWT Klystron Drivers (not shown)

Eight 75 MW PPM Klystrons

Delay Line Distribution System (2 Mode, 4 Lines)

Eight Accelerator Structure Sextets

510 MW

396 ns

Single Mode Extractor

Klystron RF Pulse
75 MW, 3168 ns


11.4 GHz RF Source

2 Mode
Launcher

Beam Direction →

Six 0.9 m Accelerator Structures
(85 MW, 396 ns Input Each)

58.6 m








R&D Overview

- RF System Critical-Path R&D
 - Develop Induction Modulator (High Efficiency, Low Cost)
 - Produce a Robust 75 MW PPM Klystron
 - Demonstrate High Pulse Energy Operation of DLDS
 - Attack Structure Gradient Problem on Several Fronts
- RF System Validation ('String-Test')
 - System Test (600 MW, 3.2 μ s pulses) at NLCTA
 - Full Scale Induction Modulator
 - Eight 75 MW PPM Klystrons
 - Multi-Mode DLDS (2 of 4 Arms Terminated in Loads)
 - Twelve 0.9 m Long, 150° Phase Advance per Cell Structures.



NLCTA Power Source: Conventional Line-Type Modulator Driving Two Klystrons





Induction Modulator 10 Core Test Setup

Generated 22 kV, 6 kA,
3 μ s Pulses




MetGlas Cores

Capacitors

IGBTs

Gallery Prototype




- Desktop Modulator
- Solid State 10-Stack installed by Gallery line-type PFN unit.
- 22 kV => 330 kV via 15:1 Xfmr.
- Prototype currently at 255 kV @ 2.2 μ sec @ 120 PPS.




Induction Modulator Prototype

'Four Dog' Test (NLC Operation)

- Four 5045 Klystrons (Eight 75 MW PPMs)
- 380kV, 420 A Each (500 kV, 250 A)
- 640 MW, 4 μ s pulse (1000 MW, 3 μ s Pulse)
- 307 kW Ave. @ 120 PPS (360 kW)






Full Scale Induction Stack
(Tested w/o oil at 75 kV, 1.1 kA)



Eight Klystron Induction Modulator

Estimated Efficiency = 75–80 % (\approx 60% for Line-Type)

Cost/Joule < 1/2 of Line-Type







Modulator Summary

- Modulator development proceeding toward qualification of a full power 8-Pack prototype.
- Gallery test setup will give first measure of performance under realistic conditions.
- 4-Dog tests in Summer 2001 will give first opportunity to study arcing in a 4-tube setup. After testing at SLAC, modulator will be shipped to FNAL.
- DFM design will build on 4-Dog experience: LLNL-BN will lead this effort in 2001. Goal is to complete System Test Version by end of 2002.



X-Band (11.4 GHz) KLYSTRONS

Solenoid Focused
Solenoid Power = 25 kW

Periodic Permanent Magnet (PPM) Focused



Axial Magnetic Field ≈ 2 KG RMS
(≈ 5 KG for Solenoid Focusing)



NLCTA Klystrons: 50 MW XL4's


Solenoid Focused ($\mu P = 1.2$, 4-Cell TW Output Cavities)

10 Built - Operated about 10 khrs Total @ 60 Hz

Few Failures - Leaks / Broken Windows: Now Using

Higher Power Window Design



Planning Test at 75 MW, 3 μs @ 120 Hz






SLAC 75 MW PPM Klystron Program

XP1: After a Number of Fixes,
Achieved Stable Performance
Over 70 MW at Twice the
Design Pulse Length (3 μ s,
Which Was Modulator Limited)




- XP3: Next Generation Tube Designed for Manufacturability
- Incorporate Lessons Learned from XP1.
 - Diode Version Has Been Successfully Tested.
 - Klystron to be Tested in September.

RF Pulse Compression at NLCTA (SLED II)




SLED II Operation




SLED II Layout Above the Beam Line Enclosure at NLCTA

To Transport > 200 MW, Replaced Original 'Flower-Petal' Bends and Mode Converters with the Components Shown

40 m Long, 12 cm Diameter Circular Waveguide




3 dB Hybrid Using a 'Magic Tee'




90 Degree Bend Using TE₀₂/TE₂₀ Modes

Wrap Around Mode Converter




NLC RF Distribution


Switch Power Using a
'Cross Potent' Two-Mode Hybrid



Cold-Test Model
with
Cover Removed



a)




b)

Cross Potent operation with simulated electric field illustrating launching a) TE₁₀ and b) TE₂₀ in the right over-moded rectangular port with the indicated relative phases for four equal amplitude inputs. Alternate phases of the inputs sends the power to either of the left ports.


Rectangular-to-Circular Mode Converter

Convert to Low-Loss Circular WG Modes
to Transport Power Hundreds of Meters

Electric Field Patterns



Converter Geometry



Mode Transmission Experiment at KEK




TE12 Launcher into 55 m of Circular WG



Mode Mapper at Opposite End

High Power Test of DLDS Components in NLCTA Planned for 2002






RF Distribution Summary


- Have Built High Power Hybrids and Circular-to-Rectangular Mode Converters and Tested Them to ≈ 500 MW (150 ns).
- Have Tested Polarized Mode Transmission in a 55 m Long Delay Line.
- Have Conceptual Designs for all Components in a Two-Moded DLDS Scheme.
- Have Yet to Test any Components at Full Power and Full RF Energy – To this End,
 - Will Build Two-Moded Components and Test at
 - ↳ > 600 MW (240 ns) in the NLCTA in 2002
 - ↳ 600 MW (3000 ns) in a System Test in 2003-4
- Also, Will
 - Continue Low Power Tests of Polarized Mode Generation and Transmission at KEK and FNAL.
 - Explore Feasibility of a Four Mode DLDS Scheme.

Long-Range Transverse Wakefield Suppression


Detuning: Systematically Vary Cell Dimensions to Yield a Gaussian Dipole Mode Distribution




Damping: Add Manifolds to Couple Out Dipole Power




Expected Wakefield for a Damped (DS) and a Damped Detuned Structure (DDS)





RDDS1 on Coordinate Measuring Stand
(above) and 1 of 206 Cells (below)



Rounded Damped Detuned Structure (RDDS1)

SLAC/KEK Collaboration to Improve on DDS Design:

Rounded Cell Design for Increased (19%) Shunt Impedance


Four Output Ports to Damp Both Polarizations of the Dipole Modes Near the End of the Structure

Better Optimized Dipole Mode Distribution for Detuning

High Precision Cell Fabrication ($< 1 \times 10^{-4}$ Freq Errors)

But,

Differential Expansion during Bonding & Brazing Distorted Cells: Some Corrected, Fix Remainder after ASSET Test






NLC Linac Gradient Considerations

- To minimize cost, want unloaded gradient (G_U) in the X-band linacs to be 70 +/- 10 MV/m.
- For expandability, assuming lower cost X-band power sources are available in the future, want $G_U > 100$ MV/m.
- Gradient potential: have achieved > 100 MV/m at X-band in standing wave and short (0.3 m), low group velocity ($< 3\%$) traveling wave structures.


SEM Iris Photograph



Input

1.8 m X-Band Structure


Output



Pitting on Cell Irises
After 1 khr @ <math>< 50 \text{ MV/m}</math>





Breakdown Effect on Phase Advance per Cell



Why is Most Damage at the Upstream End ?

If Breakdown is Modeled as a Load Impedance,
 Power Absorbed in the Load Scales as
 $\text{Group Velocity}^2 \times \text{Gradient}^2$






Program to Improve High Gradient Performance

- Structure parameters
 - Compare performance of traveling wave structures with different
 - ✓ Initial group velocity (5 % and 3% c)
 - ✓ Lengths (20, 50 and 100 cm).
 - Test 15 cell standing wave cavity.
- RF processing
 - Process a 1.8 m long, 12% c initial group velocity structure ‘more gently.’
 - Systematically study breakdown events (measure RF, light, sound, X-rays, currents and gas) in structures, waveguide and single cavities.
- Materials and handling
 - Improve degassing: wet H₂ fire + vacuum bake + in-situ bake test structures.
 - Measure surface cleanliness/damage with SEM and auger.
 - Test different cleaning techniques: ultra pure water rinsing, glow discharge cleaning and high pressure water rinsing.
- Theory and modeling
 - Use ‘MAGIC’ particle-in-cell code to simulate the breakdown effect on RF.

Operation History of Several Test Structures





High Gradient Summary

- Discovered RF Circuit Affects Achievable Gradient
 - Breakdown damage not just a function of surface field.
- Encouraged by Recent Low Group Velocity Structure Tests
 - Achieved gradients > 70 MV/m with no discernable damage.
 - Breakdown rate at 70 MV/m is about 1 per hour (1 in 200,000 pulses), which is marginally acceptable for the NLC.
 - Nearly all breakdown occurs near the input coupler at this gradient.
 - Will soon test high impedance coupler aimed at eliminating these events.
- If This Proves to be the Right Approach
 - Have efficient designs for 5% and 3% c group velocity structures meeting NLC short-range transverse wakefield requirements.
 - Modifications to suppress the long-range wakefield are in development.




Next Generation X-Band Structure

Increase Phase Advance to 150°/cell (from 120°/cell)

To Achieve Lower Group Velocity: 5.1 → 1.1 % (11.8 → 3.0 %)
with

Same Average Iris Radius / $\lambda = 0.18$

- Structure Length: 0.9 m (1.8 m)
- Cell Length: 10.9 mm (8.7 mm)
- Number of Cells: 83 (206)
- Input Power: 85 MW (170 MW)
- Unloaded Grad: 70.0 (72.4 MV/m)
- Es/Ea: 2.5 → 2.1 (3.0 → 2.2)



NLCTA RF System Test Setup

- Low Level RF System
- One 490 kV 3-Turn Induction Modulator
- Eight 2 KW TWT Klystron Drivers (not shown)
- Eight 75 MW PPM Klystrons
- Reduced Delay Line Distribution System (2 Mode)
- Two Accelerator Structure Sextets

